BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-10/2019-20 Dt:04-9-2019

APPROVED TENDER SCHEDULE –'B'

Item:1

Name of Work:- "Emergency work in Kempegowda ward no:01"

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri.Y.B.Ramesh	
				Rate	Rate in Words
1	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 SR 2018-19	cum	257.00	332.75	Three Hundred ThirtyTwo Paise SeventyFive Only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19	cum	257.00	91.90	NinetyOne Paise Ninety Only
3	Supplying and fixing precast rainforced concrete slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. (Drain covering slab)	sqm	526.50	2453.85	Two Thousand Four Hundred FiftyThree Paise EightyFive Only
4	Providing precast slab of 250 mm thick including cost of all materials, labour, curing, transportation, loading ,unloading,etc.,complete as per the direction of engineer in charge-	sqm	58.00	5688.90	Five Thousand Six Hundred EightyEight Paise Ninety Only

	Engaging on Hire Basis JCB including Driver/operator with fuel etc complete (SR 2018-19) Page No XLVIII code 1031)	Day	30.00	5979.75	Five Thousand Nine Hundred SeventyNine Paise SeventyFive Only
6	Engaging on Hire basis of Tractor 50 HP for Conveying of excavated and removal of Stuff from work spot (SR 2018-19) Page No XLVIII code 1024)	Day	90.00	2235.45	Two Thousand Two Hundred ThirtyFive Paise FourtyFive Only
7	Labour charges to Unskilled Mazdoor Heavy (Page no .LVI)SR 2018-19 sl No 5	Day	900.00	468.50	Four Hundred SixtyEight Paise Fifty Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.